FHWA REGION	STATE	PROJECT	
			1984

2/2

AUGLAIZE COUNTY
AUG-119-2.90
R/W PLAN

SECTION 21 — JACKSON TOWNSHIP SECTION 22 T 7S R 4E

P.I. STA. 166+67.00
SEC. CORNER Δ= 0°-11' LT.
NO STONE I. PIN & REF MONS.
FROM 1928 SURVEY

WILLIAM J. THIEMAN &
ANN M. THIEMAN

IN SEC. 22 ONLY
TOTAL TAKE 1.360 Ac.
PRO IN TAKE 0.907 Ac.
NET TAKE 0.453 Ac.

2 STY. BR. RES.

PROP R/W N 89°-25'-30" E 1316.51'
EX. R/W
PROP R/W S 89°-59'-30" W
S 89°-25'-30" W 164.00'
S 89°-25'-30" W 289.97'
S 89°-25'-30" W 650.59'
N 89°-25'-30" E 651.67'
N 89°-36'-30" E 664.97'
℄ SR-119 & SECTION LINE

1 STY. FR. RES.

ADOLPH TEBBE &
MATILDA TEBBE H & W

IN SEC. 27 ONLY
TOTAL TAKE 0.955 Ac.
PRO IN TAKE 0.458 Ac.
NET TAKE 0.497 Ac.

HENRY S. SCHMITMEYER &
THELMA R. SCHMITMEYER
VOL. 161, PAGE 448

TOTAL TAKE 0.972 Ac.
PRO IN TAKE 0.449 Ac.
NET TAKE 0.523 Ac.

SECTION 28 — JACKSON TOWNSHIP SECTION 27 T 7S R 4E

JACKSON TOWNSHIP SECTION 22 T 7S R 4E

THIEMAN FARM PARTNERSHIP
VOL. 252, PAGE 678

TOTAL TAKE 1.417 Ac.
PRO IN TAKE 0.890 Ac.
NET TAKE 0.527 Ac.

2 STY. BR. RES.

N 89°-25'-30" E PROP R/W 581.35'
N 89°-25'-30" E PROP R/W 710.97'
EX. R/W
PROP R/W S 89°-25'-30" W 1285.84'
N 89°-25'-30" E 1292.36'
℄ SR-119 & SECTION LINE N 89°-25'-30" E 1284.86'

DONALD F. THIEMAN &
JOAN M. THIEMAN
VOL. 210, PAGE 118
VOL. 258, PAGE 540

TOTAL TAKE 1.918 Ac.
PRO IN TAKE 0.885 Ac.
NET TAKE 1.033 Ac.

BY ORIG. R.R. SURVEY & R.R. ON N-S ½ SEC. LINE PLACING ¼ SEC. COR. AT STA. 193+03.94

FROM RAILROAD EAST SEE AUG-119-03.80 R/W PLAN RECORDED: VOL. 1, PAGE 66 (10-16-79)

STA. 192+75.94 — STA. 193+43.94 — STA. 192+68.44 — STA. 193+18.94 — ℄ R.R. TRACK — R.R. ℄

SCALE 1" = 50'
DRAWN 9-26-12-83
REVISED

JACKSON TOWNSHIP SECTION 27 T 7S R 4E

R/W PLAN STA. 165+00 TO STA. 195+00